


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 28 Twp. 29S Rge. 13W ~~SW~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
330' FNL; 430' FEL, SW/4
Lease Owner F. G. Holl
Lease Name Wright #1-28 Well No. 1-28
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well completed April 6, 1981
Application for plugging filed April 6, 1981
Application for plugging approved April 6, 1981
Plugging commenced 8:00 AM, April 6, 1981
Plugging completed 9:30 AM, April 6, 1981
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4725'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 520' with 50 sacks 50/50 Pozmix with 4% gel
through open ended drill pipe at 520'; heavy mud to
240' with 40 sacks through open ended drill pipe; heavy
mud to 40' with Howco plug, 1/2 sack hulls with solid
bridge and 20 sacks to surface. 10 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1981
CONSERVATION DIVISION
Wichita, Kansas 67579

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
Richard L. Mead (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Richard L. Mead
STEELING DRILLING COMPANY
Richard L. Mead, Vice President
P. O. Box 129, (Address) Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1981.

F. A. WUELLNER - NOTARY PUBLIC
My Appointment Expires Sept. 17, 1981

F. A. Wuellner
F. A. Wuellner, Notary Public.

My commission expires _____

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - WRIGHT #1-28
Located: 330' FNL; 430' FEL, SW/4, Section 28-29S-13W,
Pratt County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 28, 1981
COMPLETED: April 6, 1981

TOTAL DEPTH: 4725'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 163 Surface Soil, Sand and Shale	Ran 5 joints 10 3/4", 32# used casing. 238.16' set at 250' K.B.
163 - 253 Shale and Red Beds	Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 6:15 PM, 3-28-81, by Howco.
253 - 532 Shale	
532 - 1022 Red Beds and Shale	
1022 - 1609 Shales	
1609 - 4423 Lime and Shale	
4423 - 4510 Lime	
4510 - 4605 Lime and Chert	
4605 - 4632 Simpson	
4632 - 4725 Shale and Sand	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1981

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1 1/4° at 2186'
3/4° at 4383'