

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5-151-21648-0000

LEASE NAME Larrison

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-A

SPOT LOCATION 100' south of
W 1/2 of NE SE
SEC. 26 TWP. 29 RGE. 13 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 1-22-86

Plugging Completed 1-24-86

LEASE OPERATOR Mar Mac

ADDRESS 1026 Union Center Bldg. Wichita, Ks. 67202

PHONE # (316) 267-6065 OPERATORS LICENSE NO. _____

Character of Well Dry hole
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation None Depth to top _____ bottom T.D. PBTD 4588'

Show depth and thickness of all water, oil and gas formations. Top of cement 3940' Perfs 4507 1/2'
4531 1/2', 2 shots per foot.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	389'	8 5/8"		none
		389'	4749'			45 joints

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.


1-10-86 14 sx. sand dumped in well, sand at 4521'.
1-22-86 Dumped 70 gallons sand and 40 bbl. water in well, sand at 4425'. Dumped 4 sx. cement, 200 bbls. water, shot casing at 1858', pulled 45 jts, rigged down, moved off. 1:00 P.M. 500# max, 400# ISIP. Top hole plugging, 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, 150 sx. cement, 50/50 poz. 2% gel.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893
Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of operator) or plugging contractor
~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry
(Address) Box 847 Pratt, Kansas



SUBSCRIBED AND SWORN TO before me this 13 day of Feb., 1986

My Commission expires: Feb. 6, 1989

Dorothy M. Furgason
STATE CORPORATION Notary Public

FEB 14 1986
02-14-86
CONSERVATION DIVISION