

API NUMBER 15-151-21,778

LEASE NAME McLean

WELL NUMBER 1

SPOT LOCATION N $\frac{1}{2}$ NE NE

SEC. 28 TWP. 29S RGE. 13 (E) (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 10-30-87

Plugging Completed 1-6-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McGinness Oil Co.

ADDRESS 1026 Union Center Bldg. Wichita, Kansas 67202

PHONE # (316) 267-6065 OPERATORS LICENSE NO. 9854

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom Rotary T.O. 4644

Show depth and thickness of all water, oil and gas formations. PBTD 4620' Perfs: 4520-32, 2 shots per foot.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	350'	8 5/8	350'	0
		350'	4643'	4 1/2		66 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

10-30-87: To location, dumped 175 gallons sand in well. 10-31-87: Dumped 5 sx. cement, Electra Log shot casing at 2858', recovered 66 jts. 11-6-87: Top hole. 10-45-11-30 A.M. 3 sx. hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 1 sx. hulls, 1 plug, 125 sx. cement, 60-40 poz., 6% gel. 300-500# pump pressure, 225# shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893
 Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt

Judy Berry (employed as operator) or of plugging contractor of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry RECEIVED CORPORATION COMMISSION DEC 1 1987 CONSERVATION DIVISION Wichita, Kansas

(Address) _____



SUBSCRIBED AND SWORN TO before me this 30 day of Nov., 1987

My Commission expires February 6, 1989

Dorothy M. Furgason
 Notary Public