


WELL PLUGGING RECORD 173

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick County. Sec. 1 Twp. 26 Rge. (E) 1 (W)
Location as "NE/CNWKSWK" or footage from lines SW SW SW
Lease Owner Grahamhart-Miller Oil Company
Lease Name Deweese Well No. 11
Office Address 1005 East Second Street, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 28 19 54
Application for plugging filed February 28 (Verbal) 19 54
Application for plugging approved February 28 (Verbal) 19 54
Plugging commenced February 28 19 54
Plugging completed February 28 19 54
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider 800 Bitting Bldg, Wichita, Ks.
Producing formation Depth to top Bottom Total Depth of Well 3605 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 211',
set bottom plug with 1/2 sack
hulls and 15 sacks cement.
Filled hole with mud to 25',
set top plug at 25' with 1/2
sack hulls and 5 sacks cement.
Mud to surface.

3-9-1954

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor Graham-Messman-Rinehart Oil Company
Address 1005 East Second Street, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. Gilliland (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1005 East Second Street
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 54
Betty June Boyles Notary Public.

My commission expires September 14, 1957

PLUGGING
FILE SEC 1 T26R10
PAGE 16 LINE 21

WELL RECORD

Location: SW SW SW 1-26-111
 Sedgwick County, Kansas
 Operator: Graham-Miller Oil Company
 1005 East Second St., Wichita, Kansas
 Contractor: Graham-Messman-Fincham Oil Co.
 1005 East Second St., Wichita, Kansas
 Commenced: February 12, 1954
 Completed: February 28, 1954
 Elevation: 1350 K.F.
 Production: D & A
 Casing Record: 8 5/8" @ 220' W/150 sacks cement.

L O O

Sand & gravel	50	Shale-lime & sand	3456
Shale & clay	211	Lime	3470
Shale & lime	430	Lime - dolomite	3486
Lime & shale	639	Lime	3480
Shale & lime	750	Lime	3500
Shale & shells	1000	Shale & sandy dolomite	3517
Lime & shale	1333	Lime	3563
Shale - lime	1538	Lime - shale	3605 T.D.
Shale - lime	1610		
Lime - shale	1873		
Lime - shale	1960		
Shale - lime	2115		
Lime - shale	2360		
Lime - shale	2462		
Lime - shale	2545		
Lime - shale	2645		
Lime - shale	2723		
Lime	2733		
Lime	2840		
Lime	2942		
Lime	3012		
Lime	3062		
Lime	3132		
Chert	3178		
Lime	3210		
Lime - chert	3230		
Lime - chert	3253		
Lime - chert	3265		
Lime - chert	3300		
Lime - chert	3320		
Lime - chert	3364		
Lime - shale	3415		

T O P S

- Lansing -2373' (-1023)
- K.C. - 2507' (-1237)
- Mississippian -3094' (-1744)
- Kinderhook -3360' (-2010)
- Misner Sand -3449' (-2099)
- Viola -3461' (-2111)
- Simpson -3488' (-2138)
- Arbuckle -3571' (-2221)

The undersigned, GRAHAM-MILLER OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MILLER OIL COMPANY

By: J. A. Gilliland
 J. A. Gilliland

Subscribed and sworn to before me
 this 8th day of March, 1954.

Betty Jean Bayles
 Notary Public

My Commission Expires: September 14, 1957

PLUGGING
 FILE SEC 1 26-111
 PAGE 16 LINE 21