


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sedgwick County. Sec. 2 Twp. 27 Rge. 1W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW  
Lease Owner Drillers Production Company  
Lease Name Southwestern College #4 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 1/22/71 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 1/25/71 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3404 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	210	none
				5 1/2"	3397'	1666'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, sanded hole to 2680', set 5 sacks of cement.  
Shot pipe at 2050', 1956', 1859', 1765', 1670', pulled 53 joints. Bailed hole to 240', set 15' rock bridge to 225' and ran 3 1/2 yards of ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss. NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being personally sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of February, 19 71

[Signature]  
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
508 East Murnock, Wichita, Kansas


9

Company - DRILLERS GAS COMPANY  
Farm - Southwestern College No. 4

SEC. 2 T. 27 R. 1W  
NE NE SW

Total Depth. 3404  
Comm. 12-28-49 Comp. 2-8-50  
Shot or Treated.  
Contractor. Springer and Harper  
issued. 2-25-50

County. Sedgwick  
KANSAS



Elevation. \_\_\_\_\_

Production. Est. 25 Bbls. pr day

CASING:

8 5/8" 210' cem w/175 sx.  
5 1/2" OD 3397' cem w/250 sx.

Figures indicate Bottom of Formations.

surface clay, sand	65
shale, shells	210
anhyd., shale	390
shale, shells	515
shale, lime	950
shale, shells	1400
lime, shale	1450
shale, shells	1675
lime	1715
lime, shale	2415
shale, shells	2525
shale	2590
lime	2770
lime, shale	2830
shale	2860
shale, shells	3005
shale	3062
lime Miss.	3065
lime	3295
lime, shale	3387
lime.	3397
lime	3404
Total depth	

Tops:	
Kansas City	2582
Mississippi	3061
Viola	3388
Simpson	3393

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas