

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Sedgwick County, Sec. 2 Twp. 27 Rge. XEX 1 (W)

Location as "NE/CNW/SW" or footage from lines 330 NSL & 50 EWL of SE SW

Lease Owner DRILLERS PRODUCTION COMPANY, INC.

Lease Name Southwestern College Well No. 5

Office Address Insurance Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 19 19 53

Application for plugging filed April 29 19 53

Application for plugging approved April 30 19 53

Plugging commenced May 4 19 53

Plugging completed May 8 19 53

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production April 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Kansas City Depth to top 2710 Bottom 2717 Total Depth of Well 3413 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
K.C.		2590		8-5/8"	220'	None
Miss.		3071		5-1/2"	3400'	2155'
Viola		3395				
Smp.		3397				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 2760' to 2700' and ran 6 sacks of cement. Bailed hole to 220', set rock bridge to 205' and ran 15 sacks of cement. Mudded hole to 30', set 10' rock bridge and ran 5 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. R. Bickford, Jr. (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. R. Bickford, Jr.
Insurance Bldg., 212 N. Market, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27 day of May, 19 53

My commission expires August 13, 1955

24-2675-S 2-52-20M

PLUGGING
FILE SEC 2 T 27 R 1W
BOOK PAGE 98 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1953
CONSERVATION DIVISION
Wichita, Kansas
5-20-1953


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - THE DRILLERS GAS COMPANY
Farm - Southwestern College No. 5

SEC. 2 T. 27 R. 1W
SW SE SW
330' N, 50' E of SWc SE SW

Total Depth. 3410 $\frac{1}{2}$ PB 3398
Comm. 4-18-50 Comp. 5-19-50
Shot or Treated 1000 acid
Contractor. Springer and Harper
Issued. 7-15-50

County. Sedgwick
KANSAS



Elevation. 1331

Production. dry

Figures Indicate Bottom of Formations.

sand, clay	60
shale, shells	214
anhyd.	320
lime	385
lime, shale	475
lime	560
lime, shale	1250
sand	1280
lime, shale	1565
shale, shells	1685
lime	1705
shale	1760
lime	1820
lime, shale	1850
lime	2090
lime, shale	2325
lime	2375
lime, shale	2540
shale	2595
lime	2765
shale	2820
lime	2900
lime, shale	3073
lime	3110
lime chert	3165
lime	3285
lime, shale	3375
shale	3395
Viola	3399
sand	3401
lime ?	HFV 3410 $\frac{1}{2}$
Total depth	PB 3398'

Tops:
Kansas City 2590
Mississippi 3071
Viola 3395
Simpson dolomite 3397

DST 2710-17, open 20"
rec. 45' Hy oil and gas cut
mud and 25' free oil, BHP 325#.
7 ϕ 3395-96 $\frac{1}{2}$ '
Swbd 13 Bbl oil and 146 Bbl water, 3 $\frac{1}{2}$ hrs.
Lane Well plug 2770 $\frac{1}{2}$ '.
19 ϕ 2709-15, 1000 acid.
Pumped 13 BHPH, no oil, dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 2 T. 27 R. 1W
BOOK PAGE 18 LINE 13