

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 7 1962

12-7-62

Nov. 27, 1962. CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kalso of Knight Caseing Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Darrell Kalso guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Co. Inc.

Complete Address: Union Center Bldg. Wichita, Kansas.

Lease Name: Kenney#1 Well No. #1

Location: C-NW-NE Sec. 26 Twp. 27S Rge. 16 (E) (W)X

County Kiowa Co. Total Depth 4725' Oil Well Abandoned

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Darrell Kalso was instructed to plug the well as follows:

4650' of 4 1/2" long string cemented with 100 sacks cement.

Top Perforation at 4573'. Sanded to 4570' & 3 sacks cement.

257' of 8 5/8" surface pipe circulated with cement.
Hole filled to 200' with mud, 10' rock bridge, and 20 sacks

cement. Hole filled to 40' with mud, 10' rock bridge and 10

sacks cement to base of cellar.

Very truly yours,

Hanna Justice
 Conservation Division Agent