

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 7 September, 19 58, authorized the following plugging operation:

Operator's Full Name: Walters Drilling Co.

Complete Address: 1/2 Honaker Davis Co., 2008 Lakin, Great Bend, Kans.

Lease Name: Rothmeier Well No. 1

Location: CNE NW Sec. 27 Twp. 27 Rge. 16 (E) (W) X

County: Kiowa Co. Total Depth: 4732

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

315' of 8 5/8" surface casing circulated with cement. Sand to 4450'
with 3 sack cement dumped with dump bailer top perf. Pull pipe and
fill hole to 315 with heavy mud. Set rock bridge and dump 20 sack
cement from rock bridge. Heavy mud to 40'. Set rock bridge from 40'
Cement to base of cellar.

Very truly yours,

Signed: _____

Conservation Division Agent

RECEIVED
 STATE CORPORATION COMMISSION

SEP 20 1958

CONSERVATION DIVISION
 Wichita, K.