

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

28-December 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Buch Hunch of Kelco Casing has this date requested permission to plug the following described well:

Operator's Full Name: Imperial Oil Co.

Complete Address: 720 4th Financial Center Wichita Kansas 67202

Lease Name: F.N.C. Well No. 1-28

Location: 1/4 E of C. - SW - NE 1/4 Sec. 28 Twp. 27 Rge. 16 (E) (W)

County: Nowa Total Depth: 4735'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hunch was instructed to plug the well as follows:

There is 361' of 8 5/8" surface casing cement circulated with 300 skb of cement. There is 4734' of 4 1/2" production pipe cemented with 150 skb of cement with top of cement to 4065'. They plugged well back to 4673'. With perforations at 4662' to 4672'. 1st plug sand off bottom to 4600' put 4 skb of cement on top of it. 2nd plug with 15 skb jell 5 skb hulls 10 skb jell release rubber plug then 125 skb cement. That should fill hole from 425' to 0'. Plug ging accomplished by Jim Cementing

Very truly yours,

Paul Luther
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
1-5-82
JAN-5 1982

There was 2790' of 4 1/2" production pipe recovered
Cement used was 5450 pause with 4 3/4 jell 3 3/4 c.c.
Marfanin pump pressure was 800 lbs, shut in at 300 lbs.

CONSERVATION DIVISION
Wichita Kansas