



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

10-11-**RECEIVED**
STATE CORPORATION COMMISSION

OCT 14 1981
CONSERVATION DIVISION
Wichita, Kansas

10-14-81

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-097-20, 797-0000

Dear Sir:

Mr. Bill Nelson of Mustang Drilling has this date requested permission to plug the following described well:

Operator's Full Name: F. & M. Oil Co.

Complete Address: 421-Union Center, Wichita Kansas 67202

Lease Name: Frankhauser Well No. 1

Location: S 1/2 of SE-NW Sec. 32 Twp. 27 Rge. 16W (E) (~~W~~)

County: Kiowa Total Depth: 4785'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Nelson was instructed to plug the well as follows:

There is 286' of 8 1/8" surface casing cemented/circulated with 175 lbs of cement. Elevation at ground level is 2109'. 1st plug circulated heavy mud for 10 min at 800' then pumped 40 lbs of cement to this level. 2nd plug pushed rubber plug to 275' and pumped 35 lbs of cement on top of rubber plug. 3rd plug 40' to 0' with 10 lbs cement on solid bridge. Then put 5 lbs in rat hole & 10 lbs cement in 90'-5" water well. Plugging accomplished by Sun Cementing out of Great Bend Texas.

Very truly yours,
Paul Luthi
Conservation Division Agent