

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1978 8-10-78
(of this well)
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil Co.

Complete Address Box 784 St. Bend, Kans. 67530

Lease Name Turd Well No. 1-35

Location C-S-E-SW- Sec. 35 Twp. 27 Rge. 16 (E) (W) 4

County Seiwa Total Depth 4697

Abandoned Oil Well Gas Well 4 Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Felso Casing Pulling

Address Box 176 Chase Kans. 67524 License No. 683

Operation Completed: Hour 3 pm Day 4 Month 8 Year 1978

The above well was plugged as follows:

406' - 8" casing w/ 300 sack Cement - 4 1/2" casing set @
4696' w/ 200 sack Cement - plug back to 4680' Top prof
4636' - 40' - Swabs stuck @ 4200' w/ 8" frack sand on
top of swabs. Mix & dump 4 sack cement on top of sand w/ dump
hailer. Pull 3616' 4 1/2" casing. mix & pump 3 sack hulla - 25 sack
gel - release plug. mix & pump 125 sack 50 parts top casing.

Pumped by

Sen Cementing Co - St. Bend, Kans. 67530

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-10-78

INV NO. 7825-u