

4-27-82

RECEIVED
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3
Rev. 1-8-82

APR 27 1982

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT REPORT

20846

API Number 15-097-20864-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Graves Drilling Co.

Complete Address 910 Union Center, Wichita, Kansas 67202

Lease Name Ward Well No. 1

Location C-SW-NW Sec. 35 Twp. 27 Rge. 16 (East)(West)

County Kiowa Total Depth 4770'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was equipped to test but never produced

Plugging Contractor Clark Corporation

Address 107 West Fowler, Medicine Lodge, Kans 67104 License No. 583

Operation Completed: Hour: 9:45 AM. Day: 22 Month: April Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They set 4768' of 4 1/2" production pipe with 4265' ^{Top} of cement out side of pipe. They plugged back to 4728' perforated from 4647' to 4665'. 1st plug sanded off bottom hole back to 4600' put 4 sky of cement on top of the sand. 2nd plug allied cementing pumped through head on surface casing 6 sky hulls 10 sky Jell and 150 sky of cement. They had recovered 2647' of 4 1/2" production pipe. The plugging was accomplished by Clark Corporation with Allied cementing pumping the cement. ~~Amount of Surface Casing: 434' of 8 5/8" cement circulated (over)~~

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 4-27-82
INV. NO. 9989-01

Signed: _____
Conservation Division Agent

The cement used was Common Cement with
3% C. C. They shut it in at 700 lbs.