

14 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1962
12-7-62
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bowers Drilling Co. Inc.

Complete Address: Union Center Bldg. Wichita, Kansas.

Lease Name Kenney #1 Well No. #1

Location C-NW-NE Sec. 26 Twp. 27S Rge. 16 (E) (W) X

County Kiowa Co. Total Depth 4725'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Caseing Pulling Co.

Address: Chase, Kansas. License No. 436

Operation Completed: Hour 2:PM Day 5 Month Dec Year 1962

The Above well was plugged as follows:

4650' of 4 1/2" long string cemented with 100 sacks cement. Top perforation
at 4573' Sanded to 4570' & 3 sacks cement. 257' of 8 5/8" surface pipe
circulated with cement. Hole filled to 200' with mud, 10' rock bridge,
and 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge & 10
sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Herman Justus
Well Plugging Supervisor

DATE 12/11/62
INV. NO. 6193-42