

[Handwritten signature]

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 127-35 County: Kiowa

Location: CNE NW Sec. 27 Twp. 27 Rge. 16 (E) (W) X

Name of Field: _____ Total Depth: 4732

I have this date completed supervision of plugging of:

Lease Name: Rothmeier Well No. 1

Operator's Full Name: Walters Drilling Co.

Complete Address: % Honaker Davis, 2008 Lakin, Great Bend, Kans.

Plugging Contractor: Southwest Pipe Pulling Co.

Address: Great Bend, Kans. License No. _____

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 11:30 PM Day 11 Month September Year 1958

The above well was plugged as follows:

315' of 8 5/8" surface casing circulated with cement. Hole was sanded to
4450' and 3nsack cement dumped with dump bailer. Pipe was shot off at 3395'.
Pipe pulled ans hole filed with heavy pip mud.to 315'. Rock bridge set
from 315' with 20 sack cement dump top bridge. Heavy mud to 40'. Rock
bridge set from 40' with cement to base of celar.

Signed: *[Signature]*
Conservation Division Agent

Reviewed: *[Signature]*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 27 T 27 R 16
BOOK PAGE 27 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1958
CONSERVATION DIVISION
Wichita, Kansas