

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued December 21, 1967.

Operator's Full Name Glen Armour

Complete Address: 2421 Tenth St., Great Bend, Kansas 67530

Lease Name Fruit Well No. # 1

Location SW SW Sec. 28 Twp. 27 Rge. 16 (E) (W) W

County Kiowa Total Depth 4699'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Russ Casing Pulling, Inc.

Address: Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 3:30PM Day 26th Month December Year 1967

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 240 sacks. 4697' of 4 1/2" long string,  
cemented with 125 sacks. Plug back T.D. 4654'. Top perforation 4636'. Bottom of  
the hole was sanded to 4600', and cemented with 4 sacks, through the dump bailer,  
with cement from 4600' to 4550'. 3000' of 4 1/2" long string was recovered from the  
hole. Bridge plug was pushed in fluid to 260', rock bridge from 260' to 250'. 5  
sacks of cement with 8% Calcium Chloride was mixed in a barrel, and put on plug at  
250', through the dump bailer, and let set for 3 hours. Hole was bailed dry, and  
20 sacks of cement was added to the plug, with cement from 250' to 175'. Hole was  
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks,  
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: Archie Elving  
Well Plugging Supervisor

DEC 28 1967

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 12/28/67

INV. NO. 6996-W