

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,713 ⁰⁰⁰⁰

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720, 4th Financial Center, Wichita Kansas 67202

Lease Name F.M.C. Well No. 1-28

Location 110' E of C-5 W-NE 1/4 Sec. 28 Twp. 27 Rge. 16 (East)(West)

County Kiowa Total Depth 4735'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chaso Kansas 67524 License No. 681

Operation Completed: Hour: 3:00 P.M. Day: 31 Month December Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 361' of 8 1/2" surface casing cement circulated with 300 skb of cement. There is 4734' of 4 1/2" production pipe cemented with 150 skb of cement with top of cement at 4065'. They plugged well back to 4673'. With perforations at 4662' to 4672'. 1st plug sandbed off bottom to 4600' put 4 skb of cement on top of it. 2nd plug with 5 skb Jell, 5 skb hulls, 10 skb Jell, then released rubber plug and followed up with 125 skb of cement. That should fill hole from 425' to 0'. The plugging was accomplished by Sun Cementing

There was 2790' of 4 1/2" production pipe recovered. Cement used was 50/50 sand with 4% Jell & 3% C.C. Maximum pump pressure was 800 lbs that was used.

I hereby certify that the above plugging instructions were given as herein stated.

DATE 1-20-82

JAN - 5 1982

Signed: Paul Luthi
Conservation Division Agent

INV. NO. 8976-W

CONSERVATION DIVISION
Wichita, Kansas

1-5-82

18.3.89