

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
12-6-65  
DEC - 6 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Eason Oil Company

Complete Address: Box 18755, Oklahoma City, Oklahoma

Lease Name Tuller, Block 1 Well No. # 1-30

Location C SE NW Sec. 30 Twp. 27 Rge. 16 (E) (W) W

County Kiowa Total Depth 4780'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gayle E. Toland

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 3:00 PM Day 1st Month Dec. Year 1965

The Above well was plugged as follows:

246' of 13 3/8" surface pipe, cement circulated. 2400' of 8 5/8" surface  
pipe, cemented with 100 sacks. 4778' of 2 7/8" tubing, cemented with 75  
sacks. 2 7/8" cast iron plug was set at 4750'. 3025' of 2 7/8" long string  
was recovered from the hole. 1320' of 8 5/8" surface pipe was recovered  
from the hole. Hole was squeezed. 20 sacks of Gel-Mud and 200 sacks of  
cement was pumped in surface pipe, through an 13 3/8" swage. A wiping  
plug was run between the mud and the cement.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 12/6/65

INV. NO. 2342-W