

J
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mr. J. Mark Richardson M.P. & B.D. Gilbert

Complete Address 220 W.O. Garvey Bldg. Wichita, Ks

Lease Name Smitherman Well No. 1

Location C NE/SE Sec. 31 Twp. 28 Rge. 27 16 (E) (W) W

County Kiowa Total Depth 4750

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 9:00 AM Day 2 Month 11 Year 1970

The above well was plugged as follows:

280 ft of 8 5/8 surface pipe cemented with 240 sacks, Circulated.

4750 ft of 5 1/2 long string cemented with 150 sacks. Top perf. 4040 ft.

Sand back to 4000 ft, 5 sacks cement with bailer. Pulled 2900 ft of 5 1/2.

Set 10 ft rock bridge at 260 ft, Fill hole with 4 yds redimix to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russ B. Bickert
Well Plugging Supervisor

DATE 11/4/70

INV. NO. 2806-u