

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20797-0000

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name F. & M. Oil Co.

Complete Address 422 Union Center, Wichita, Kansas 67202

Lease Name Fankhauser Well No. 1

Location S 1/2 of SE-NW Sec. 32 Twp. 27E Rge. 16 (East) (West)

County Kiowa Total Depth 4785'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Mustang Drilling Co.

Address Box 1425 Great Bend Kas. 67503 License No. \_\_\_\_\_

Operation Completed: Hour: 11:30AM Day: 11 Month: October Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is 286' of 8 1/8" surface casing cement circulated with 175 bbls of cement. Elevation at ground level is 2109'. 1st plug circulated heavy mud for 10 min. then pumped 40 bbls of cement to 800'. 2nd plug pushed rubber plug to 275' and pumped 35 bbls of cement on rubber plug. 3rd plug 40' to 0' with 10 bbls of cement on solid bridge. Then put 5 bbls cement in rat hole & 10 bbls of cement in water well 90' with 5" casing. Plugging accomplished by Sun Cement Co. out of Great Bend Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Paul Luther  
Conservation Division Agent  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1981  
10-14-81  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 11-19-81  
NV NV 8228-W