

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC 22 TWP 27 RGE. 16W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Pender

Operator M B Pender - M.R.C. Address 910 Petroleum Bldg
Wichita Kans.

Field _____ County Kiowa

Total Depth 4945 Feet.

Plugging Contractor M B Pender. Stanton Cox well

Plugging Contractor's License No. Dry Rotary

Address Wichita Kansas.

(Describe briefly the manner in which the well was plugged)

8 3/4" S.P. 350' C.W.C. hole filled with
heavy rotary mud to 350' set plug
run 20 lb cement through drill pipe
mud to 35' set plug run 10 lb cement
top.

M. L. Pices
District Conservation Agent

Date 7-19-55

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 22 T. 27 R. 16W
BOOK PAGE 136 LINE 32

7-22-55

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **M. B. Armer**

SEC **22** T. **27S** R. **16W**

FARM **Reeder**

NO **1.**

LOC **27**

TOTAL DEPTH **4947**

COUNTY **Kiowa**

COMM. **6/30/55**


COMP. **7/19/55**

KANSAS

SHOT OR TREATED

CONTRACTOR **M. B. Armer**

ISSUED



CASING

20	10	
15	8	350'
12	6	
13	5	

ELEVATION **2091** N.D.

PRODUCTION **D.**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	170
Shale & Shells	250
Sand	270
Red Bed	315
Sand	345
Red Bed	1010
Anhydrite	1035
Sand & Shale	1370
Shale, Shells & salt	1730
Shale - Shells	1875
Shale - Lime	2035
Shale	2105
Shale & Lime	3020
Lime	3040
Shale & lime	4141
Lime	4483
Lime & Shale	4560
Miss. Chert	4635
Cherty Lime	4637
Shale & Lime	4703
Cherty lime & Shale	4740
Lime	4797
Shale & lime	4848
Sand	4857
Sand & Shale	4887
Lime	4947

FORMATION TOPS

W. R.	3890	KIOWA	4550
DOWN LITE	4050	VALLEY	4729
LANSING	4066	WINDY HILLS	4816
BASE KANSAS CITY	4365	BEAUFORT SAND	4841
COGLIMBATE	4541	ANDACOLE	4904
MISISSIPPI	4569		

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

PLUGGING
 FILE SEC 22 T. 27S R. 16W
 BOOK PAGE 36 LINE 32

By Merk Britting

NOTARY PUBLIC IN AND FOR THE STATE OF KANSAS
 My Comm. Expires 10/13/56

Subscribed and sworn to before me, a notary public, in and for said County and State this 22nd day of July, 1955.

Lorraine M. Johnson

My Commission expires October 13, 1956.