

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed April 5, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woods Petroleum Corporation

Complete Address: P. O. Box 18667, Oklahoma City, Oklahoma

Lease Name Reeder Well No. # 1

Location NE SW Sec. 22 Twp. 27 Rge. 16 (E) (W)W

County Kiowa Total Depth 4760'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company

Address: 617 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 10:15AM Day 30th Month April Year 1967

The Above well was plugged as follows:

370' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
level in the hole was at 320', 1st cementing plug, bridged with 1/2 sack
of hulls on fluid at 320', and cemented with 35 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 5 sacks.
This cementing was done by Sun Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/2/67

INV. NO. 5147-W