

91


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sedgwick County, Sec. 2 Twp. 27 Rge. 1 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NE  
Lease Owner Drillers Production Company  
Lease Name Ott #7 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved 19\_\_  
Plugging commenced 1/19/71 19\_\_  
Plugging completed 1/21/71 19\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice  
Producing formation Depth to top Bottom Total Depth of Well 2703 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	212	none
				4 1/2"	2696'	2144'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 2690', set 3 sacks of cement. Shot pipe at 2213', 2150', pulled 69 joints. Bailed hole to 240', set 15' rock bridge to 225' and ran 3 1/2 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 27th day of January, 1971

My commission expires 2/15/71

Notary Public.

R


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
508 East Murdock,                      Wichita, Kansas

Company- DRILLERS PRODUCTION CO., INC.  
Farm- Ott                                      No. 7

SEC. 2      T. 27      R. 1W  
SE SW NE

Total Depth. 2703'  
Comm. 12-26-56                      Comp. 2-6-57  
Shot or Treated.  
Contractor. Springer & Harper  
Issued. 3-9-57

County Sedgwick  
KANSAS



Elevation. 1328' RB

Production. 25 BOPD

**CASING:**

8 5/8" 212' w/200 sx cem.  
4 1/2" 2696' w/100 sx cem.

Figures indicate Bottom of Formations.

soil-sand	55
shale-sand	198
lime	415
lime-shale	780
shale-shells	1055
shale-lime	1470
shale-shells	1730
shale-lime	1850
lime	2180
lime-shale	2410
lime	2430
lime-shale	2470
shale-shells	2585
lime	2703
Total Depth	

**TOPS:**

Kansas City lime	2585
Oolitic Zone	2695

Drill deeper w/cavle tools 2698-2703'  
Bail 27.9 \* 6.7 GWPH  
Put on pump 9 BO & tr. WPD Natural

Acidized w/5000 gals:

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas