


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-173-01847-0000

NORTH



Locate well correctly on above
Section Plat

SEDGWICK County. Sec. 1 Twp. 26S Rge. 1 ~~XXX~~ (W)
Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner S. & S. Pipe & Supply Reed Well No. 5
Lease Name _____
Office Address P.O. Box 2513 Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-13-29 19____
Application for plugging filed 3-3-54 19____
Application for plugging approved 3-4-54 Jan. 14 19 54
Plugging commenced _____ 19____
Plugging completed Aug. 12 19 55
Reason for abandonment of well or producing formation SWDW

If a producing well is abandoned, date of last production SWDW 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes
Ruel Durkee

Name of Conservation Agent who supervised plugging of this well

Producing formation Dolomite Depth to top 3355 Bottom 3359 Total Depth of Well 3359 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				20"	49'	None
				15 1/2"	218'	218'
				8 1/2"	3025'	100'
				6 5/8"	3348'	100'
				12 1/2"	1315'	1315'
				10"	2090'	2090'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 6 sacks of cement at 3340'. Due to pipe being eaten up caused by corrosion only recovered approximately 100' of 8" and 100' of 6 5/8. Pumped in 100 sacks of cement and displaced to about 100' by Halliburton Oil Well Cementing Co. and put 20 sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Bert Self

Address

Hutchinson, Kansas

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 55

My commission expires August 12, 1957

Notary Public.



RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1955

CONSERVATION
Wichita

9-14-55

15173-61847-0000

Completion Report - Lea K. Reed #5, located SE of SW of SE. 1-26-1W.
Sedgwick Co., Kas.

Contractor - Herndon Drilling Company, Standard Tools.

Date Spudded - 9-26-29.

Date of Completion - 11-13-29.

Actual Depth - 3359'.

Initial Production - Swabbed 567 Bbls. in 20 Hrs.

Top of Dolomite - 3355'.

Nature of Strata	From	To	Remarks
Sand	0	57	
Blue Slate	57	90	20" Set at 49'
Shale	90	150	
Broken Lime	150	160	
Shale	160	180	
Slate	180	218	15" Set at 218'
Shale	218	250	
Lime	250	265	
Shale	265	280	
Broken Lime	280	340	
Lime	340	380	
Gray Shale	380	400	
Red Rock	400	410	
Lime	410	415	
Shale Gray	415	450	
Red Rock	450	465	
Lime Shale	465	475	
Lime	475	500	
Blue Shale	500	510	
Lime	510	535	
Broken Lime	535	635	
Shells and Slate	635	655	
Shale	655	685	
Sand	685	705	
Shale	705	715	
Red Rock	715	730	
Shale	730	750	2 B.W. at 690'
Lime	750	755	
White Slate	755	765	
Lime	765	785	
Shale	785	825	
Sand	825	850	
Shale Dark	850	860	
Lime	860	870	
Shale White	870	885	
Lime	885	895	
Sandy Shale	895	920	
Blue Shale	920	930	
Dark Shale	930	970	
Sand	970	990	
Lime	990	1020	10 B. W. at 975'
Blue Shale	1020	1030	
Lime	1030	1035	
Blue Shale	1035	1150	
Lime	1150	1155	
Shale	1155	1170	
Red Rock	1170	1175	
Gray Shale	1175	1185	
Blue Lime	1185	1195	
Blue Shale	1195	1260	
Lime	1260	1270	
Shale Dark	1270	1305	
Sandy Shale	1305	1315	
Lime	1315	1320	
Shale	1320	1360	
Lime	1360	1370	
White Shale	1370	1395	
Lime	1395	1400	

RECEIVED
OCT 11 1929
U.S. GEOLOGICAL SURVEY

PLUGGING
12 1/2" 3526-T-26-1W
BOOK PAGE 22 LINE 14

Completion Report - Lea K. Reed #5, Continued.

15-173-01847-0000

<u>Nature of Strata</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale	1400	1415	
Lime	1415	1420	
Gray Shale	1420	1430	
Lime	1430	1440	
Shale	1440	1460	
Lime	1460	1465	
Light Shale	1465	1480	
Shale	1480	1490	
Lime	1490	1495	
Shale	1495	1510	
Lime	1510	1520	
Shale	1520	1550	
Lime	1550	1605	
Blue Shale	1605	1620	
Sand (water)	1620	1630	
Blue Shale	1630	1655	
Lime	1655	1695	1 1/2 B. W. P. H. 1620' to 1630'
Sandy Shale	1695	1705	
Black Shale	1705	1715	
Blue Shale	1715	1730	
Sandy Lime	1730	1735	
Lime	1735	1785	8 B. W. from 1730' to 1735'
Sandy Shale	1785	1835	
Lime	1835	2020	8 B. W.
Black Slate	2020	2030	
Lime	2030	2090	
Shale	2090	2100	10" Set at 2090'
Sandy Shale	2100	2130	
Gray Shale	2130	2240	
Sandy Shale	2240	2245	
Lime	2245	2250	
Blue Shale (cave)	2250	2260	
Lime	2260	2270	
Gray Shale	2270	2320	
Shale	2320	2345	
Lime	2345	2355	
Black Shale	2355	2385	
Lime	2385	2385	
Sand (water)	2385	2395	
Lime	2395	2450	2 B. W. P. H. at 2385' - 2395'
Shale	2450	2460	
Lime	2460	2500	
Shale	2500	2540	
Lime Shells	2540	2560	
Lime	2560	2725	1 Bailer oil 2530' to 2590'
Shale	2725	2770	6 B. W. at 2660'
Sandy Lime	2770	2785	
Shale	2785	2830	
Shells and Shale	2830	2880	
Lime	2880	2885	
Shale	2885	2895	
Shale and Shells	2895	2970	
Lime	2970	2980	
Shale	2980	3005	
Pink Rock	3005	3025	8 1/2" Set at 3025'
Broken Lime	3025	3030	
Lime	3030	3070	
Sandy Lime	3070	3080	
Lime	3080	3260	
Shale	3260	3355	6-5/8" Set at 3348'. Cemented with 60 sacks oilmax.
Dolomite	3355	3359	

<u>Total Depth</u>		<u>CASING RECORD</u>			
<u>Size.</u>	<u>Weight.</u>	<u>Amt Run.</u>	<u>Amt Pulled.</u>	<u>Amt Left in.</u>	<u>Sacks Cement used.</u>
20"	90.0#	49'	None	49'	
15 1/2"	70.0	218'	218'	None	
12 1/2"	50.0	1315'	1315'	None	
10"	40.0	2090'	2090'	None	
8 1/2"	32.0	3025'	None	3025'	
6-5/8"	24.0	3348'	None	3348'	60