

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-20,285-00-00

LEASE NAME LARRISON

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1980
1650 Ft. from S Section Line

1980 1650 Ft. from E Section Line

CNW-SE
 SEC. 31 TWP. 29S RGE. 13 (W)

LEASE OPERATOR HINKLE OIL CO.

COUNTY PRATT

ADDRESS 150 NORTH MAIN #1016 WICHITA, KS. 67202

PHONE#(316) 267-0231 OPERATORS LICENSE NO. 5290

Date Well Completed _____

Character of Well OIL

Plugging Commenced 6-7-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-9-94

The plugging proposal was approved on 6-8-94 (date)

by DODGE CITY OFFICE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation BRIDGE PLUG ~~XXXXXXXXXXXX~~ AT 4690. Bottom T.D. 4775

Show depth and thickness of all water, oil and gas formations. PERFS: 4654-57
4734-36
4739-41

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	247	10 3/4	247	0
		0	4774	5 1/2	4774	92 jts. 3000 ft.
				3/4"		185 rods
				2 3/8"		150 jts. tubing

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

6-7-94: RIGGED UP, PULLED & LAYED DOWN RODS & TUBING. 6-8-94: LOG TECH SET PLUG AT 4600'
DUMPED 2 SX. CEMENT ON TOP OF PLUG. SHOT CASING OFF AT 3000 FT., PULLED & LAYED DOWN 92 JTS. OF
5 1/2" CASING. RIGGED DOWN & MOVED OUT. 6-9-94: ALLIED CEMENT TOP HOLE PLUGGED WITH 300# HULLS
10 SX GEL, 5 SX CEMENT, 10 GEL, 200# HULLS, 175 SX CEMENT, 60 40 POZ, 6% GEL. MAX 600#. ISIP 200#.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5895

Address BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HINKLE OIL CO. 07.07.94

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

(Employee of ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) c/o PWS, INC.



SUBSCRIBED AND SWORN TO before me this 5th day of July, 1994

Dorothy M. Ferguson
 Notary Public

My Commission Expires February 6, 1997