

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

**JUN 21 2001**  
WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-20354-00-00

LEASE NAME Larrison

WELL NUMBER #2

2970 Ft. from (S) Section Line

990 Ft. from (E) Section Line

SEC. 31 TWP. 29S RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-15-01

Plugging Completed 5-17-01

**TYPE OR PRINT**  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pratt Well Service, Inc.

ADDRESS P.O. Box 847 Pratt, KS 67124

PHONE#(620) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no, do not have logs

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4763

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

Formation	Content	From	To	Size	Put In	Pulled out
Simpson Sand				5 1/2"		42 Jts

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
5/15 - set cast iron BP @ 4650'. Dumped 25sx cement. Loggers cut 2000' - 5 1/2". pulled 1-10'x5 1/2" sub, 42 Jts-5 1/2" casing. Lost 7-9 Jts in hole- left them. 5/16 - welder cut braden head off, welded plate and collar on 10 3/4" surface pipe. dumped 300# hulls. started to pump get when welded plate and collare blew off-injured cementer from Acid Services.  
5/17 - dumped 10 sx gel, 50 sc cement, 10 sx gel, 100# hulls, 150 sx cement on top, 60/40 pox, 6% gel

Name of Plugging Contractor Pratt Well Service, Inc.

License No. 5893  
KANSAS CORPORATION COMMISSION

Address P.O. Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt

Amy S. Robertson, Production Clerk (Employee of Operator) or (Operator) c  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts  
statements, and matters herein contained and the log of the above-described well as filed the  
the same are true and correct, so help me God.

(Signature) Amy S. Robertson

(Address) P.O. Box 847 Pratt, KS 67124

**KEVIN C. GATES**  
Notary Public - State of Kansas  
My Appt. Expires 3/13/04

SUBSCRIBED AND SWORN TO before me this 31 day of May, 2001

Kevin C. Gates  
Notary Public

My Commission Expires: 3/13/04

OR