

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 6 TWP. 27S RGE. 16W E/W
Location as in quarters or footage from lines:
C SW/4

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Berexco Inc.
 Lease Name Mull #1 Well No. 1
 Office Address 970 Fourth Financial Center, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed November 6, 1981
 Application for plugging filed November 6, 1981
 Plugging commenced 12:15 PM, November 6, 1981
 Plugging completed 2:00 PM, November 6, 1981
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom _____ T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 450' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 1050' with 50 sacks Howco Common Cement
with 2% gel and 3% cc through open ended drill pipe;
heavy mud to 430', shoved rubber plug to 430', spotted
40 sacks through open ended drill pipe at 430'; heavy mud
to 40' with Howco rubber plug at 40'; 10 sacsks to surface;
5 sacks in rat holr, 5 sacks in mousehole and 5 sacks in
water well.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 17 1981
 11-17-81
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 81.



[Signature]
 Agnes D. Wurst, Notary Public.

My Commission expires: _____

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- MULL #1
Located: C SW/4, Section 6-27S-16W, Kiowa County, Kansas

OWNER: Berexco Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 28, 1981
COMPLETED: November 6, 1981

TOTAL DEPTH: 4800'

LOG

CASING RECORD

0 - 228 Shale
228 - 452 Sand and Shale
452 - 1056 Shale
1056 - 1080 Anhydrite
1080 - 1500 Shale
1500 - 2210 Shale and Lime
2210 - 2234 Shale
2234 - 4745 Lime and Shale
4745 - 4800 Lime

Ran 11 joints 8 5/8", 20# new casing.
436.17' pipe set at 450' K.B. Cemented
with 300 sacks 60/40 Pozmix with 3% cc.
Plug down at 9:30 PM, 10-28-81, by Howco.

Plugged.

Deviation Surveys: 1 1/2° at 2234'
1° at 4592'

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1981

CONSERVATION DIVISION
Wichita, Kansas