

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23484-00-01

Spot: NESWNWNW

Sec/Twnshp/Rge: 15-7S-21W

800 feet from N Section Line,

650 feet from W Section Line

Lease Name: BUTCH A OWWO

Well #: 1-15

County: GRAHAM

Total Vertical Depth: 3727 feet

Operator License No.: 9408

Op Name: TRANS PACIFIC OIL CORPORATION

Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3742		215 sx
SURF	8.625	221		160 sx

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/06/2015 9:00 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: MONTE

Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 735-9405

Proposed Wash Down well dry hole drilled to 3727'. CIBP set at 3620'.  
Plugging Ordered 350 sx 60/40 pozmix 4% gel cement, 13 sx gel and 300 # hulls.  
Method: Port collar at 1715' w/425 sx cement.

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/06/2015 12:30 PM

KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

**Perfs:**

Ran tubing to 3590' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1795' and pumped 165 sx cement. Good circulation of cement. Pulled tubing out and topped off w/20 sx cement. Backside is full of cement to surface.


GPS: 39.45009 -099.65565

Remarks: SWIFT CEMENT TICKET # 28687

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

7/29/15 CKM

JUL 06 2015

KCC WICHITA

JUL 14 2015

RECEIVED

Form CP-2/3