

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-20725-00-02
Spot: SWSWSW Sec/Twnshp/Rge: 3-15S-27W
370 feet from S Section Line, 5021 feet from E Section Line
Lease Name: CLIFFORD A Well #: 1
County: GOVE Total Vertical Depth: 4360 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1950		600 SX
SURF	8.625	259		175 SX
T1	2.875	1534		

Well Type: SWD UIC Docket No: D23162.0 Date/Time to Plug: 07/09/2015 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: TANNER Company: TREK AEC, LLC Phone: (620) 793-2146

Proposed Plugging Method: Ordered 100 sx 60/40 pozmix 4% gel cement.
Perforations at 1543' - 1643'.
2 7/8" tubing cement in hole at 1534'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2015 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran 1" pipe to 1925' and pumped 45 sx cement. Good circulation of cement. Pulled 1" out of tubing. Tied on to tubing and squeezed w/25 sx cement. Shut in with 1200 psi. Tied on to backside and squeezed with 15 sx cement. Shut in with 100 psi.

GPS: 38.77208 -100.31789

Perfs:

Top	Bot	Thru	Comments
1543	1643		

Remarks: SWIFT CEMENT TICKET # 28689

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

7/29/15 cmm

CM

Received
KANSAS CORPORATION COMMISSION

JUL 17 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUL 14 2015

7-17-2015

unc