

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-26518-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 2-14S-17W  
3900 feet from S Section Line, 550 feet from E Section Line  
Lease Name: KUHN Well #: 1-A  
County: ELLIS Total Vertical Depth: 3510 feet

Operator License No.: 3194  
Op Name: TRI UNITED, INC  
Address: 950 270TH AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.625	3502		130 SX
SURF	8.765	218		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2015 12:20 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED INC. Phone: (785) 628-3670

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 200 # hulls and 17 sx gel. Perforations at 1090' w/150 sx CWC  
Perforations: 3263' - 3332 LKC, 3486' - 3494' ARB, 3502' - 3510' ARB  
CIBP at 3460' and 3500'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2015 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 5 1/2" casing with a swedge and pumped 50 sx cement w/200 # hulls mixed in, followed by 15 sx gel (2 sx gel short from order), followed by 165 sx cement. Pumped well to pressure with 500 psi. Shut in pressure 500 psi. Rigged to 8 5/8" casing and pumped 15 sx cement to pressure with 100 psi. Shut in pressure 100 psi.  
GPS: 38.86764 -09917161

Perfs:


Top	Bot	Thru	Comments
32635	32695		
3502	3510		
3486	3494		
3328	3332		
3263	3332		
3220	3224		

Remarks: QUALITY WELL SERVICE TICKET # 6364

Plugged through: CSG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

7/29/15 CKM

(M)

KCC WICHITA

Form CP-2/3

JUL 09 2015

JUL 14 2015

RECEIVED