

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
.266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21272-00-00
Spot: NENESE Sec/Twnshp/Rge: 28-14S-28W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: BRIGGS A Well #: 1
County: GOVE Total Vertical Depth: 4108 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4108		175 SX
SURF	8.625	262		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2015 12:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method:	Ordered 250 sx 60/40 poizmix 4% gel cement, 8 sx gel and 400 # hulls. Port Collar at 2000' w/300 sx cement. Perforations at 3979' - 3982'.
---------------------------	--

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2015 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3980' and pumped 8 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2015' and pumped .170 sx cement. Good circulation of cement. Pulled tubing out and topped off with 20 sx cement. Cement is at surface on backside.

GPS: 38.80656 -100.43011


Remarks: SWIFT CEMENT TICKET # 28621

Plugged through: TBG

7/29/15 CKM

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 14 2015

JUL 17 2015

CONSERVATION DIVISION
WICHITA, KS