

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23616-00-00
Spot: SESWNW Sec/Twnshp/Rge: 36-16S-25W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SCHUCKMAN D Well #: 1
County: NESS Total Vertical Depth: 4485 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	4.5	1876		250sx cement
PROD	4.5	4469		225 SX
SURF	8.63	277		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2015 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE, INC. Phone: (785) 798-3641

Proposed Plugging Method: Pump bottom w/ 25sx cement with 100# hulls. Run tubing to 1900' and circulate cement to surface. Check backside

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2015 9:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

Pumped bottom at 4459' w/ 15sx gel, 20sx cement. Pulled tubing to 1900' circulated cement to surface w/ 125sx cement and 100# hulls. Pulled tubing and topped off with 35sx cement. Filled backside with 5sx cement

Remarks: CEMENT: 60/40 POZMIX 4% GEL BY SWIFT SERVICES

Plugged through: TBG

District: 01

Signed Larry Adams PERTZ
(TECHNICIAN)

RECEIVED
JUL 13 2015 2ms
KCC DODGE CITY

KCC WICHITA
JUL 24 2015
RECEIVED