

2 050458

Plugged 10-31-86 82 R

API NUMBER 15- 173-20,153-0000

SE SE SW, SEC. 35, T 27 S, R 2 W/R

330 FSL feet from S section line

330 FEL feet from E section line

Lease Name Herndon Well # 1

County Sedgwick 115.38

Well Total Depth 3,550 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 486

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Operator: Rains & Williamson Oil

Name & Address 435 Page Court

220 West Douglas

Wichita, KS 67202

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Co. Tools License Number 5146

Address

Company to plug at: Hour: Day: 31 Month: 10 Year: 19 86

Plugging proposal received from

(company name) (phone)

were: 4 1/2" casing set at 3,549 with 100 sacks perf. at 3,496' to 3,500'. Sand back to 3,450' and dump four sacks cement. Shut and pull pipe. Plug top with 12 sacks gel., three sacks hulls and 175 sacks cement.

Plugging Proposal Received by Ron Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:00 AM Day: 31 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT Sand back to 3,450 and dumped four sacks of cement. Shot and pulled 1,800 feet of 4 1/2" casing. Squeeze 8 5/8 with 15 sacks gel, three sacks hulls and 170 sacks cement.

11-20-1986

NOV 20 1986

Remarks: B-J Tilon 284340 60/40 Poz mix. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-21-86

INV. NO. 15398

Signed Glenn Ward (TECHNICIAN)