

2 090007

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
NE, SEC. 11, T. 27 S, R. 1 W/E XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5463

_____ feet from N/S section line
_____ feet from W/E section line

Operator: Samson Resources Co.
Name & Address Valley Center, Ke.

Lease Name Roenback Well # 1
County: Sedgwick
Well Total Depth 2750 ^{89.38} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 185

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing & Pulling License Number 6050

Address P.O. Box 176, Chase, Kansas

Company to plug at: Hour: _____ p.m. Day: 7 Month: 6 Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) _____

were: sand back to 2660' -- 55 sacks cement on top of sand -- bridge at 275'
and redi mix

RECEIVED
STATE CORPORATION COMMISSION

_____ recovered about 1690' -- 54 joints left bailer in hole

JUN 20 1984
6-20-1984
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 7 Month: 6 Year: 19 84

ACTUAL PLUGGING REPORT

The bottom of the hole was filled with sand to 2660' and 5 sacks of cement was spotted on top of the sand through the bailer. The pipe was shot off, and 1690' of 5 1/2" was recovered. While coming out of the hole with the last load from the boiler, the bottom of the surface was hooded, snapped the cable and a piece of 5 1/2" 31' was lost in the hole. AN wire line was sent to 400', no trace ~~XXXXXX~~ of the 5 1/2". Left the 5 1/2" in the hole. The top was plugged with 11 yards of readi-mix.

Remarks: Walt Keeler Redi Mix #7489
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-27-84

Signed Daniel Wentz
(TECHNICIAN)

INV. NO. 2159