

2 090059

672-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20, ~~671~~
CSESE, SEC. 18, T 27 S, R. 4 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

660 feet from N/E ~~XXXXXX~~ line
660 feet from W/E ~~XXXXXX~~ line

Operator: Diamond Shamrock
Name & Address: Box 23
Lunadian, TX

Lease Name Mary Kay Kobler # 1
County Sedgwick
Well Total Depth 4225 137.31 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Kaw Drilling License Number _____

Address _____

Company to plug at: Hour: 10:00a.m. Day: 10 Month: 10 Year: 19 84

Plugging proposal received from Pete Coats

(company name) _____ (phone) _____

were: 35 sacks at 4150'; 25 at 1150'; 35 at 360'; 25 on plug at 60'; 10 in
rat 60-40, 2% gel, 2% cc

RECEIVED
STATE CORPORATION COMMISSION
10-18-1984
OCT 18 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Stan Marcotte
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8:30p.m. Day: 10 Month: 10 Year: 19 84

ACTUAL PLUGGING REPORT Fill hole with heavy mud. Ran drill pipe to 4150' and spotted
35 sacks of cement, pulled pipe to 1150' and spotted 25 sacks of cement. Pulled
pipe to 360' and spotted 35 sacks of cement. Set wood and rubber plug at 60' and
spotted 25 sacks of cement. Circulated 10 sacks of cement in the rat hole
60-40, 2% gel, 2%cc

Remarks: Haliburton Ticket #890693
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-29-84

Signed Daniel White
(TECHNICIAN)

INV. NO. 4499

WK
KP