

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10965-00-00
Spot: NESWSW Sec/Twnshp/Rge: 35-29S-13W
1022 feet from S Section Line, 4421 feet from E Section Line
Lease/Unit Name: KEYES Well Number: 3
County: PRATT Total Vertical Depth: 4528 feet

Operator License No.: 3688
Op Name: 4-D PETROLEUM CONSULTANTS,LLC
Address: 40351 NE 5TH AVE.
PRESTON, KS 67583

Conductor Pipe: Size feet: 147.16
Surface Casing: Size 8.625 feet: 900 WITH 450 SX CMT
Production: Size 2.875 feet: 4526 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/17/2002 3:00 PM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: TOM POST Company: 4 D PETROLEUM Phone: (620) 546-3004

Proposed Plugging Method: FILL 2 7/8" TUBING WITH CMT AND PUMP 150 SX CMT DOWN 2 7/8" & 8 5/8" ANNULUS.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/17/2002 3:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4370-4380'. PUMPED DOWN 2 7/8" CASING WITH 100# HULLS IN WITH 100 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 0#. STANDING FULL WITH CMT. PUMPED DOWN 2 7/8"/8 5/8" ANNULUS WITH 100# OF HULLS IN WITH 150 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN WITH 200#.

RECEIVED
OCT 17 2002
KCC WICHITA
10-17-2002

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED SEP 30 2002

DATE 10-18-02

INV. NO. 2003060659

Form CP-3/3