

1 010188

DEC 4 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,747-00-00
NE SW NW, SEC. 35, T 29 S, R 13 W/E
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Irene Well # 1-35

Operator: McGinness Oil Company
Name & Address 1026 Union Center Bldg.
Wichita, KS 67202

County Pratt 151.78

Well Total Depth 4670 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 931

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:25 p.m. Day: 4 Month: 12 Year: 19 86

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: Perfs at 4566-4580' Elevation 1868'GL

1st plug sand back to 4445' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 4 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4445' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cmeent, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

STATE CORPORATION COMMISSION

DEC 9 1986

12-09-86

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Recovered 3330' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (Date) observe this plugging.

Signed Jack R. Luthi
(TECHNICIAN)

DATE 12-10-86

INV. NO. 15576