

1 060609

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,626 - 00-00

NE NE SW, SEC. 34, T 29 S, R 13 W X

2183 feet from S section line

2805 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Larrison Well # 1

Operator: Vincent Oil Corporation

County Pratt 152.75

Name & Address 125 North Market

Well Total Depth 4700 (Simpson) feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 3:00 am Day: 1 Month: July Year: 19 85

Plugging proposal received from Tony Ernst

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1827' Anhydrite 750'

1st plug at 750' with 50 sx cement

2nd plug at 430' with 50 sx cement solid bridge -

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:00 am Day: 1 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 750' with 50 sx cement, 2nd plug at 430' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement. Plugged water well with 5 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 11 1985

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.

(If additional description is necessary, use BACK BY PHONE TO BUREAU OF CONSERVATION, WICHITA, KANSAS)

observe this plugging.

DATE 7-17-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 8981 7-1