

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20374-00-01
Spot: SWSW Sec/Twnshp/Rge: 33-29S-13W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: FINCHAM Well Number: C-1
County: PRATT Total Vertical Depth: 4725 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: 155 N. MARKET - SUITE 800 PO BOX 4
WICHITA, KS 67201

Production Casing Size: 5.5 feet: 4717 WITH 175 SX CMT
Surface Casing Size: 8.625 feet: 265 WITH 250 SX CMT

#153⁵⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2003 1:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4500' & 5 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: _____ WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/10/2003 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PERFS AT 4580-4610'. SANDED BACK TO 4500' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. DID NOT CIRCULATE. 2ND PLUG AT 290' WITH 50 SX CMT. BROKE CIRCULATION WITH WATER. SPOT PLUG. NO RETURNS. SHUT DOWN TO LET CMT SET. 06/10/03: RUN TUBING IN & TAG CMT TOP AT 260'. AT 260' SPOT 50 SX COMMON W/3% CC CMT WITH 50# OF HULLS MIXED IN. 3RD PLUG AT 90' SPOT 25 SX COMMON CMT.

RECEIVED
JUN 19 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT. RECOVERED 2430' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
6-19-03
2003061654

Form CP-213