

To: 1 010082
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-156-01648-00-00
328 R
API NUMBER 15- N/A
100 S of W/2
NE SE, SEC. 28, T 29 S, R 13 W/4
1880 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9854
Operator: Marmac Petroleum Co.
Name & Address: 1026 Union Center Building
Wichita, KS 67202

Lease Name Larrison Well # 1-A-1
County Pratt 154.34
Well Total Depth 4749 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:40 am Day: 29 Month: January Year: 19 86

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4748' PBD 4588' Perfs at 4507-13'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 29 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dump 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 400 psi

FEB 4 1986

Remarks: Recovered 1854' 4 1/2" casing. Used 50/50 Pozmix 2% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 6 1986
INV. NO. 12408

Signed Jack K. Luthi
(TECHNICIAN)