

1 010189

DEC 4 1986

API NUMBER 15- 151-21,768 - 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C E/2 E/2 SW SEC. 28, T 29 S, R 13 W/E

1320 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Wright Well # 1

Operator: McGinness Oil Company

County Pratt 153.21

Name & Address 1026 Union Center Bldg.

Well Total Depth 4714 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 3:45 p.m. Day: 4 Month: 12 Year: 19 86

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: Perfs at 4204-14' Elevation 1900'GL

1st plug sand back to 4128' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

and pump 125 sx cement.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 4 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4128' and dump 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and pumped 125 sx cement.

DEC 9 1986 17-09-86

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 750 psi and shut in 250 psi.

Remarks: Recovered 1860' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 12-10-86

Signed Jack Luthi (TECHNICIAN)

INV. NO. 15577