

1 040003

11-6-87

API NUMBER 15- 151-21,778-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 NE NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 28, T 29 S, R 13 W/EX
4950 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9854

Lease Name McLean Well # 1

Operator: MarMac Petroleum Company
Name & Address 1026 Union Center Building
Wichita, KS 67202

County Pratt 150.93
Well Total Depth 4644 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:45 a.m. Day: 6 Month: 11 Year: 19 87

Plugging proposal received from Fred Mease

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4643' PBD 4620' Perfs at 4520-32'

1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 6 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED
11-16-87

Pumping pressure 300-500 psi and shut in 350 psi.

NOV 16 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2858' of casing
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

NOV 20 1987

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE _____

INV. NO. 18910

11-6