

1040977 6-22

15151-30910-00-01

API NUMBER 15- 4/14/61 completion date

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION App. SW SW SE, SEC. 28, T 29 S, R 13 W/E  
130 S. Market, Room 2078  
Wichita, KS 67202

300 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3553  
Operator: Citation Oil & Gas Corporation  
Name & Address: 8223 Willow Place S., Ste. 250  
Houston, TX 77070

Lease Name Moore Well # 1  
County Pratt  
Well Total Depth 4715 153.24 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 953

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Mikes Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 22 Month: 6 Year: 19 95

Plugging proposal received from Richard McIntyre  
(company name) Mikes Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 4710' w/135 sx cement, PBD 4444', Perfs at 4411-4388', 4474-4488',  
CIBP at 4450' w/6' of cement on top, cement plug at 4505-4530'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer,  
2nd plug at 980' with 50 sx cement, 3rd plug at 400' with 40 sx cement,  
3rd plug at 40' with 10 sx cement, Gel spacer between plugs.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2 p.m. Day: 22 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of sand  
bridge through bailer; Spotted plugs through 4 1/2" casing: with gel spacer between plugs:

2nd plug at 980' with 50 sx cement,  
3rd plug at 400' with 40 sx cement,  
4th plug at 40' with 10 sx cement.

STATE CORPORATION COMMISSION

JUN 30 1995

06-30-95  
CONSERVATION DIVISION  
WICHITA KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2137' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 7-7-95  
INV. NO. 43042

Signed *Stephen Pfeifer*  
(TECHNICIAN)