

1 051357

10-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,057-0000

C SW, SEC. 25, T 28 S, R 21 W/E

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Chalfant Well # 1

Operator: Halliburton Oil Producing Co.

County Ford 164.15

Name & Address P.O. Box 10

Well Total Depth 5051 feet

Stafford, KS 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 524

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 17 Month: 10 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 5026' w/125 sx cement, Open hole at 5026-51'

1st plug pump 2 sx hulls and 50 sx cement to 4900',

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3 p.m. Day: 17 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 50 sx cement to 4900',

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

OCT 22 1990  
10-22-1990

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3530' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 10-29-90

INV. NO. 29753