

1050262

20339

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,399-00-00
NE SE _____, SEC. 8, T 28 S, R 24 (W/2)

TECHNICIAN'S PLUGGING REPORT

_____ feet from N/S section line
_____ feet from W/E section line

Operator License # _____

Lease Name Bell Well # 1-8

Operator: Sabine Corporation
Name & Address 2905 First Street
Woodward, OK 73801

County Ford
Well Total Depth 5407 175.73 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 539

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Reeves & Wilson, Inc. License Number 6083

Address Box 963, Woodward, OK 73802

Company to plug at: Hour: 4:00 pm Day: 20 Month: June Year: 19 84

Plugging proposal received from Sid Wilson

(company name) Reeves & Wilson (phone) 405-677-8347

were: 5 1/2 set at 5403' 300' of 5 1/2 stuck at 1560' PBSD with CIBP at 3250.

Perfs - 2772-78' 1st plug at 2724' with CIBP and 2 sx cement

2nd plug at 1560' with 50 sx cement

3rd plug at 570' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

Plugging Proposal Received by Richard W. Ducey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:00 pm Day: 20 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 5403' 300' of 5 1/2" stuck at 1560' PBSD with

CIBP at 3250', Perfs 2772-78' - 1st plug at 2724' with CIBP and 2 sx cement, 2nd

plug at 1560' with 50 sx cement, 3rd plug at 570' with 50 sx cement, 4th & 5th plugs -

solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Reeves & Wilson

(If additional description is necessary, use BACK of this report)
CONSERVATION DIVISION
Wichita, Kansas

INVOICE (did not observe this plugging.)

Signed Richard W. Ducey
(TECHNICIAN)

DATE 7-3-84 JUL 24 1984

INV. NO. 2273 6-20