

2090008

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
S/2 SESW SEC. 2, T 27 S, R 1 W/EX

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5463

Lease Name College Well # 1

Operator: Samson Resources
Name &
Address Valley Center, Ks.

County Sedgwick

Well Total Depth 2719 88.37 feet

Conductor Pipe: Size 10 3/4" feet 175

Surface Casing: Size 7" feet _____

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing and Pulling License Number 6050

Address P.O. Box 176, Chase, Ks.

Company to plug at: Hour: 11:00p.m. Day: 5 Month: 6 Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso Casing & Pulling (phone) 398-2457

were: sand back to 2650' 75 sacks cement - bridge at 250' - bail hole
dry and pump redi-mix to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00p.m. Day: 6 Month: 6 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 2650' and
7 sacks of cement were spotted on top of sand through the bailer. The 7' long
string was stuck and was unable to pull. The top was plugged with 175 sacks of
class "A" cement, 2%cc, 5% gilsonite. Instant shut in pressure 200 lb.

Remarks: United Cement ticket #7583 175 sacks; 5% gilsonite; 2%cc
(If additional description is necessary, use BACK of this form.)

INVOLCED
I (~~did~~) observe this plugging.

DATE 6-29-84

Signed Don Thompson
(TECHNICIAN)

INV. NO. 2161