

2090010

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 200' SWS/2NESW SEC. 2, T 27 S, R 1 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OLD WELL

TECHNICIAN'S PLUGGING REPORT

Operator License # 5463Operator: SAMSON RESOURCES CO.Name & Address VALLEY CENTER, KS.Lease Name College Well # 6County SEDGWICKWell Total Depth 3397 110.40 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 206Abandoned Oil Well X Gas Well Input Well SWD Well D&A Other well as hereinafter indicated Plugging Contractor KELSO CASING & PULLING License Number 6050Address P.O. BOX 176, CHASE, KS.Company to plug at: Hour: P.M. Day: 12 Month: 6 Year: 19 84Plugging proposal received from NORMAN VOTH(company name) KELSO CASING AND PULLING (phone) were: sand back to 3025' -- dump 5 sacks cement on top of sand --bridge and 275' -- dump redi-mix to surfacePlugging Proposal Received by DON THOMPSON
(TECHNICIAN)Plugging Operations attended by Agent?: All XX Part None Operations Completed: Hour: 9:30p.m. Day: 14 Month: 6 Year: 19 84ACTUAL PLUGGING REPORT THE BOTTOM OF THE HOLE WAS FILLED WITH SAND TO 3025'AND 5 SACKS OF CEMENT WAS SPOTTED ON TOP OF SAND THROUGH THE BAILER.THE PIPE WAS SHOT OFF, AND 2247' OF 5 1/2" WAS RECOVERED. THE HOLE WASBAILED TO 275'. THE TOP WAS BRIDGED AT 275' AND 4 1/2 YARDS WASCIRCULATED TO SURFACE.RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1984

Remarks: WALT KEELER TICKET #16831

CONSERVATION DIVISION

INVOICED

(did / did not) observe this plugging.

DATE 6-27-84INV. NO. 2160Signed David Wertz
(TECHNICIAN)

WL