

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20504-00-00  
Spot: CN2NWNE Sec/Twnshp/Rge: 1-26S-1W  
330 feet from N Section Line, 3300 feet from W Section Line  
Lease/Unit Name: SCHNITZLER Well Number: 3  
County: SEDGWICK Total Vertical Depth: 3445 feet

Operator License No.: 6804  
Op Name: LACHENMAYR OIL CO.  
Address: 904 EMMALINE  
NEWTON, KS 67114

Conductor Pipe: Size 13.375 feet: 123 811.96  
Surface Casing: Size 8.625 feet: 203 110 SX CMT  
Production: Size 5.5 feet: 3443 200 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/16/2002 4:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: HOWARD LACHENMAYR Company: LACHENMAYR OIL CO. Phone: (316) 284-7150

Proposed Plugging Method: Sand to 3,320' and top with 5 sxs. cement. Shoot casing off. Pull casing to 260' and circulate cement to the surface.

Plugging Proposal Received By: DAVE WERTZ Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 01/16/2002 6:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,200' and topped with 5 sxs. cement. Shot casing off at 2,216'. Pulled casing to 260' and circulated 152 sxs. cement to the surface.

RECEIVED  
KCC DISTRICT #2

FEB 07 2002

WICHITA, KS

2-7-2002

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED. INVOICE #3728.

Plugged through: CSG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICE Form CP-2/3

DATE Feb 7 02

INV. NO. 2002061349