

11-6-87

1 040004

API NUMBER 15- 151-20,481-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NW, SEC. 32, T 29 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

3410 feet from S section line

4840 feet from E section line

Operator License # 5056

Lease Name Lee Well # 1-32

Operator: F.G. Holl Company

County Pratt 155.87

Name & Address P.O. Box 780167

Well Total Depth 4796 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 6 Month: 11 Year: 19 87

Plugging proposal received from Fred Mease

(company name) Pratt Well Service (phone) 5893

were: 4 1/2" at 4790' PBSD 4698' Perfs at 4578-96, 4600-09' Elevation 1951' GL

1st plug sand back to 4525' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:30 a.m. Day: 6 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4505' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls and 125 sx cement.

11-06-87 NOV 6 1987

CONSERVATION DIVISION
Wichita, Kansas

Pumping pressure 300-350 psi and shut in 225 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2431' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED Reserve this plugging.

DATE NOV 20 1987

INV. NO. 18906

Signed Stephen J. Pfeiffer (TECHNICIAN)

11-6