

99

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Drillers Prod. Co. Inc
Complete Address 480 Natl. Bk. Bldg. Wichita Kan 67202
Lease Name 0 H Well No. H 5
Location S 22 N 22 E. Sec. 2 Twp. 27 Rge. 1 (E) (W) ←
County Sedgewick Total Depth 2707
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Co.
Address Chase Kansas License No. 436
Operation Completed: Hour 4 PM Day 27 Month 1 Year 1971

The above well was plugged as follows:

205 ft of 10 in. surface pipe (sic) with 230 lbs
Cement. 7" casing set at 2699. Cemented with
200 lbs Cement. 6 ft open hole. Sand to 2670'
46 lbs. Cement. 1680 ft of 7" pipe pulled.
Mud to 240 ft. Rock Bridge to 225 ft.
45 yds of Ready Mix to Surf.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Harmon Justice
Well Plugging Supervisor

DATE 1-29-70
INV. NO. 2720-E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 208 East Murdock, Wichita, Kansas




Company- THE DRILLERS PROD. CO.
 Farm- Ott No. 5

SEC. 2 T. 27 R. 1W
 SW NW SE

Total Depth. 2707
 Comm. 10-10-51 Comp. 1-2-52
 Shot or Treated.
 Contractor. Springer & Harper
 Issued. 2-16-52

County Sedgwick
 KANSAS



Elevation. 1327 RB

Production. Pmp. 25 bbls.

Figures Indicate Bottom of Formations.

sand	55
shale & shells	180
anhydrite	240
lime & shale	485
lime	535
lime & shale	595
lime	630
lime & shale	690
lime	720
lime & shale	1130
shale	1315
sand lime & shale	1395
shale	1445
shale & shells	1560
lime	1620
shale	1655
lime	1825
lime & shale	1870
lime	2115
lime & shale	2130
shale	2270
shale & lime	2305
lime	2365
shale	2423
lime	2450
lime & shale	2480
shale	2587
lime	2707
Total Depth	

Tops:
 Kansas City 2584

DD 2705 1/2
 500 acid
 3000 acid
 PB 2700
 Sqz 250 sks cement
 DD 2707
 15 # 2699 1/2 - 2704 1/2
 500 Acid
 1/2 BO & 5 1/2 BWPH
 1000 Acid

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 14 1970
 CONSERVATION DIVISION
 Wichita, Kansas