

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date August 14, 19 58, authorized the following plugging operation:

Operator's Full Name: Rine Drilling Co.

Complete Address: 420 Union Center, Wichita, Kans.

Lease Name: Jem Well No. 1

Location: NW NW SE Sec. 28 Twp. 29 Rge. 13 (E) (W) W

County: Pratt Total Depth: 4718

Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Cover perforations with sand and dump 5 sack cement with dump bailer.

Fill hole with heavy mud to 200'. Set rock bridge at 200' and

dump 20 sack cement. Heavy mud to 35'. Set rock bridge and fill

surface casing to base of cellar with cement.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1958
08-29-58
CONSERVATION